OFFICE OF THE INSPECTOR-GENERAL OF EDUCATION IN MYSORE, BANGALORE.

Notification dated 10th December 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Inspector-General of Education in Mysore, Bangalore, up to 30th December 1925, for the construction of a building for the Primary Boys' School at Halekal, Jagalur Taluk, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1926.

2. The plans, detailed estimate and conditions may be seen at the Office of the Inspector-General of Education between the hours of 12 noon and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Inspector-General of Education. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit
Vide Abstract.		

4. Each tender must be accompanied by a receipt for having deposited a sum of Rs. 50 in the State or other Government Treasuries in cash or Government Promissory Notes, as earnest money, and be superscribed 'Tenders for construction of a building for the Primary Boys' School at Halekal,' in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Inspector-General of Education in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, providing for a deposit of 5 per cent of the estimated cost of the work, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Office of the Inspector-General of Education in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Primary School at Halekal, Jagalur Taluk, Chitaldrug District :—

No.	Items of work	Per	Quantity
1	Earthwork excavation	C.yd.	72
2	Stone jelly in chunam concrete	C.ft.	591
3	Burnt size stone in mud	"	1,679
4	Burnt brick in mud	"	2,515
5	Burnt stone slabs roughly dressed and fixing, complete	S.ft.	161
6	Burnt brick in chunam pillars plastering, etc., complete	No.	6
7	White and colour washing two coats	Sqr.	39·59
8	Chunam plastering	"	39·59
9	Honney wood work wrought and put up	C.ft.	115·05
10	Roofing with 1st class Mangalore tiles on teak reepers, complete	S.qr.	19·38
11	Ridge tiles set in cement	R.ft.	124
12	Teakwood doors with battened shutters, hinges 5 bolts, etc., complete ..	S.ft.	46
13	Teakwood windows with battened shutters ½" iron bars hinges, complete ..	"	54
14	Chunam borders over gable ends with plastering, complete	R.ft.	40
15	Burnt brick in chunam coping to the compound wall, complete	"	54
16	Teakwood gate with iron fittings, complete	S.ft.	44
17	Chocolate painting, two coats	S.qr.	2·43
18	Constructing gate pillars with brick in chunam, ornamental caps, etc., complete ..	No.	2
19	Tarring to wood work, two coats	Square	14·54
20	Cement pointing to basement	"	4·78

Notification dated 10th December 1925.

Notice is hereby given that sealed tenders will be received at the Office of the Inspector-General of Education in Mysore, Bangalore, up to 30th December 1925, for the construction of a building for the Primary Boys' School at Medikerepura, Chitaldurg Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1926.

2. The plans, detailed estimate and conditions may be seen at the Office of the Inspector-General of Education between the hours of 12 noon and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Inspector-General of Education. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit
	Vide abstract	

4. Each tender must be accompanied by a receipt for having deposited a sum of Rs. 50 in the State or other Government Treasuries in cash or Government Promissory Notes, as earnest money, and be superscribed 'Tenders for the construction of a building for the Primary Boys' School at Medikerepura' in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Inspector-General of Education in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : providing for a deposit of 5 per cent of the estimate cost of the work ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the office of the Inspector-General of Education in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a Primary School at Medikerepura, Chitaldrug Taluk :—

No.	Items of work	Per	Quantity
1	Earthwork excavation	C.yds.	72
2	Stone jelly in chunam concrete	C.ft.	591
3	Burnt size stone in mud	,,	1,679
4	Burnt brick in mud	,,	2,515
5	Burnt stone slabs roughly dressed fixing, complete	S.ft.	161
6	Burnt brick in chunam pillars plastering, etc., complete	No.	6
7	White and colourwashing two coats	Sqr.	39·59
8	Chunam plastering	,,	39·59
9	Honney wood work wrought and put up complete	C.ft.	115·95
10	Roofing with 1st class Mangalore tiles on teak reapers, complete	Sqr.	19·38
11	Ridge tiles set in cement	R.ft.	121
12	Teak wood battened door with shutters, hinges, bolts, etc., complete,	Sq.ft.	46
13	Teak wood windows with battenad shutters ½" iron bars. hinges, complete	,,	54
14	Chunam borders over gable ends with plastering, complete	R.ft.	40
15	Burnt brick in chunam coping to the compound wall, complete	,,	51
16	Teak wood gate with iron fittings, complete	Sq.ft.	44
17	Chocolate painting 2 coats	,,	2·43
18	Constructing gate pillars with brick and chunam ornamental caps, etc., complete	No.	2
19	Tarring to wood work two coats	Sqr.	14·54
20	Chunam painting to basement	,,	4·78

K. MATTHAN,
Inspector-General of Education.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

Notice No. S. P. C. 6140, *dated 4th December* 1925.

Sealed tenders will be received in the Office of the undersigned up to 12 noon on Monday the 4th January 1926 for structural steel materials required for our Electrical Department. The quantities and specifications of the materials are noted in the subjoined statement and tenders should be sent in the form of that statement duly noting in columns left blank the rate at which the articles will be supplied. Tenders should be superscribed "Tenders for Steel Structural materials for the Mysore Government Electrical Department."

2. Earnest money of Rs. 100 which should be only by means of cheques on the Imperial or Mysore Banks without which tenders will not be considered.

3. The rates given in the schedule should be inclusive of the cost of delivery of the materials free on rails at the Closepet Railway Station, Mysore Railways, and should hold good for at least twenty-one days from the date of opening the tenders. The tender should also contain information as to the earliest possible date by which the supplies could be completed.